



Republic of the Philippines  
**PROVINCE OF ISABELA**  
City of Ilagan

*Office of the Governor*

**NOTICE OF AWARD**

April 4, 2024

**MR. WILLY C. ODIZA**

Authorized Representative

**Grains Innovation & Solution Co., Inc.**

Rm. 206 Veria Building, 62 West Avenue,  
Quezon City, 1104, Metro Manila

Dear Mr. Odiza,

We are pleased to notify you that the **Supply and Delivery of Various Rice Processing Machineries and Equipment including Installation and Commissioning /ITB No. 2024-G-004** for the Province of Isabela in the amount of **Sixty Four Million Nine Hundred Ninety Thousand Pesos & 00/100 (P64,990,000.00)** is hereby awarded to you as the Bidder with the Single Calculated and Responsive Bid.

ITEM NO.	QUANTITY/ UNIT OF ISSUE	DESCRIPTION	UNIT PRICE (P)	TOTAL BID PRICE (P)
1	2 Sets	<b>GRAIN DRYER PRE-CLEANER</b> Power: 4.4 KW Capacity: 12-15 TPH Size: 1.2 x 3.6 mt; Eccentric System Screen hole size: 12 mm diameter With Motor (3 hp; 6 poles) Input Box for Pre Cleaner: For dust collection Uniform Flow at Pre Cleaner Can work up to 35% moisture content		
2	2 Sets	<b>Wet Paddy Aspirator</b> Power: 15 kW Include: Pulley at aspirator Pulley at aspirator (drive to motor pulley) Chute for husk/empty paddy Input hopper Chute for paddy (result) and empty paddy Include pulley at motor Without motor (7.5 hp; 4 poles) To remove light impurities such as empty paddy and husk		
3	6 Sets	<b>GRAIN DRYER (131.8 KW)</b> Capacity (Paddy): 27-29 tons Power Consumption (kW): 21.97 kW Dimension: (LxWxH): 4.77x3.0x14.7 Power Consumption:		

ITEM NO.	QUANTITY/ UNIT OF ISSUE	DESCRIPTION	UNIT PRICE (₱)	TOTAL BID PRICE (₱)
		Blower left: 7.5 kW, 3 Phase, 220/440 Volts, 60 Hz Blower Right: 7.5 KW, 3 Phase, 220/440 Volts, 60 Hz Spreader: 0.75 kW, 3 Phase, 220/440 Volts, 60 Hz Cleaning fan: 1.5 kW, 3 phase, 220/440 Voltz, 60 Hz Bottom Screw: 0.75 kW, 3 Phase, 220/440 Volts, 60 Hz Rotary Valve: 0.18 kW, 3 Phase, 220/440 Voltz, 60 Hz Elevator: 3.73 kW, 3 Phase, 220/440 Voltz, 60 Hz Damper: 0.06 kW, 3 Phase, 220/440 Voltz, 60 Hz Parts Material Specification: Upper body panel and screen: 1.5mm stainless steel Bottom Hopper: 2mm stainless Steel 8" dia. Bottom screw conveyor blade: 4 mm stainless steel Stainless 201/202 Material for Upper Panels/Stiffeners Stainless 304 material for Screen Dumper is made of stainless steel CYCLOFAN Main body is made of stainless steel 201/202 material All other such as pipe and elbows are made of galvanized steel Cyclonic Husk Furnace 2000 KW Power: 13 KW Husk Consumption: 100-500 kg/h Total Electric Power: 6.5 Hp Dimensions: dia. 0.2 X 8.0 m		
4	12 Sets			
	1 Set	AUTOMATIC HOPPER SCALE Capacity: 90 cu.m.		
5	1 Set			
	1 lump sum	<b>Total</b>	<b>₱44,500,000.00</b>	<b>₱44,500,000.00</b>
6	1 Set	Bucket Elevator, Elevator 1 to Paddy Cleaner (Wet Paddy) Capacity: 40 TPH Over all height: 15 m Drive Motor Elevator belt, fastener set, belt clamp, and bucket cups Bucket Elevator Cup		
7	1 Set	Bucket Elevator, Elevator 2 to Paddy Cleaner (Wet Paddy) Capacity: 40 TPH Over all height: 15 m Drive Motor Elevator belt, fastener set, belt clamp, and bucket cups Bucket Elevator Cup		
8	1 Set	Bucket Elevator, Elevator 3 to Wet Paddy Tank (Wet Paddy)		

ITEM NO.	QUANTITY/ UNIT OF ISSUE	DESCRIPTION	UNIT PRICE (₱)	TOTAL BID PRICE (₱)
9	1 Set	Capacity: 40 TPH Over-all Height: 16 m Drive Motor Elevator belt, fastener set, belt clamp, and bucket cups Bucket Elevator Cup Bucket Elevator, Elevator 4 to Chain Conveyor 1 (Wet Paddy) Capacity: 40 TPH Overall Height: 15 m Drive Motor Elevator belt, fastener set, belt clamp, and bucket cups Bucket Elevator Cup		
10	1 Set	Bucket Elevator, Elevator 5, to Chain Conveyor 3 (Dried Paddy) Capacity: 40 TPH Overall Height: 15 m Drive Motor Elevator belt, fastener set, belt clamp, and bucket cups Bucket Elevator Cup		
11	1 Set	Bucket Elevator, Elevator 6, to Husk Tank (Husk) Capacity: Overall Height: 11 m Drive Motor: 1.5 kW Elevator belt, fastener set, belt clamp, and bucket cups Bucket Elevator Cup - 6x5		
12	1 Set	Chain elevator Elevator 7, to Ash Tank (Ash) Capacity Overall Height: 9 m Drive Motor- 1.5 kW Chain, Fastener set, belt clamp, and bucket cups Bucket Elevator cup size- 6x5		
13	1 Set	Drag Chain Conveyor (CC), CC1 to Dryers (Wet Paddy) Capacity: 40 TPH Over-all Length: 27 m Drive Motor		
14	1 Set	Drag Chain Conveyor (CC), CC2 to Batch Weigher (Dried Paddy) Capacity: 40 TPH Over-all Length: 23.5 m Drive Motor		
15	1 Set	Drag Chain Conveyor(CC), CC3 to Dried Paddy Tank (Dried Paddy) Capacity: 40 TPH Over-all Length: 12 m Drive Motor		




ITEM NO.	QUANTITY/ UNIT OF ISSUE	DESCRIPTION	UNIT PRICE (₱)	TOTAL BID PRICE (₱)
16	1 Set	Belt Conveyor(BC), BC1 to Elevator 3 (Wet Paddy) Capacity: 40 TPH Over-all Length: 10.5 m Drive Motor		
17	1 Set	Belt Conveyor (BC), BC2 to BC3 (Wet Paddy) Capacity: 40 TPH Over-all Length: 8m Drive Motor		
18	1 Set	Belt Conveyor (BC), BC3 to Elevator 4 (Wet Paddy) Capacity: 40 TPH Over-all Length: 5 m Drive Motor		
	<b>1 lump sum</b>	<b>Total</b>		<b>₱8,500,000.00</b>
19	2 Units	Wet Paddy Tank 115 cu.m 4.8x4.8x5 m Common Wall for Two Units		
	2 Sets	Manual and pneumatic slide gate		
	4 pcs	Level sensor 220 V		
	2 Sets	Blowing Fan (7.4 kW)		
20	1 Set	Buffer bin 2.2 cu.m Tank Dimension: 1500x1500x1000		
	1 pc	Manual slide gate		
21	2 Units	Dried Paddy Tank 115 cu.m 4.8x4.8x5 Common Wall for Two Units		
	2 pcs	Manual and pneumatic slide gate		
	4 pcs	Level sensor 220 V		
22	2 Sets	Receiving Hopper 2x3x2.5m Manual Intake Gate Safety barrier around the pit Ladder Civil Work		
23	1 Set	Rice Hull Receiving Hopper 1.5x1.5.2.5m Manual Intake Gate Safety barrier around the pit Ladder Civil Work		
24	2 Sets	Distribution box - 2 outlet Capacity: 40 TPH		
26	4 pcs	Manual slide gate		
27	1 set	Pneumatic Two way diverter		
28	6 sets	Pneumatic Slide Gate		
29	1 pc	Manual and pneumatic slide gate		

ITEM NO.	QUANTITY /UNIT OF ISSUE	DESCRIPTION	UNIT PRICE (₱)	TOTAL BID PRICE (₱)
30	1 set	Screw Type Air Compressor (15 kW)		
31		Dust Collecting System		
	1 lot	Dryer main fan extension duct		
	1 lot	Aspirator extension duct		
	1 set	Cyclone 1200 dia.		
	1 unit	Suction fan (7.5 kW)		
32	1 lot	Paddy Cleaner Dust Collector		
		Ducting System and accessories		
	3 sets	Cyclone 1200 mm dia.		
33	1 lot	Dryer Top Cleaning fan Dust Collector		
		Ducting System and accessories		
	6 set	Cyclone 800 mm dia.		
34	1 lot	Dryer Hot Air Ducting from furnace to dryers		
		Ducting System and accessories		
35	1 lot	Grain Dryer Dust Collector		
		Dust Collecting System		
36	1 lot	Pneumatic Line		
37		Steel Structure		
	1 lot	Steel Structure for paddy Cleaner		
	1 lot	Catwalk on the top of elevator		
	1 lot	Steel Structure for Batch Weigher		
	1 lot	Steel Structure support chain conveyor, stairs and ladders		
	1 lot	Cyclone Steel Structure		
38	1 lot	Mechanical Installation Consumables		
39	1 lot	Slide chutes and inlet + outlet hoppers system		
40	1 lot	Electric cable and cable tray		
41	1 lot	Control Panel		
42	1 lot	Repainting		
	1 lump sum	<b>Total</b>		<b>₱11,990,000.00</b>
		*** nothing follows***		
		<b>Total Bid Price</b>		<b>₱64,990,000.00</b>

You are therefore required within ten (10) days from the receipt hereof to formally enter into contract with us, and to submit the Performance Security in the form and the amount stipulated in the instruction to Bidders. Failure to comply therewith shall constitute a sufficient ground for cancellation of this award and forfeiture of your Bid Security.

Very truly yours,

  
**RODOLFO T. ALBANO III**  
 Governor 

Received by: 

WILLY C. ODIZA

Date: Apr 4, 2024